GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Rural Development – Mahatma Gandhi National Rural Employment Guarantee Scheme (MGNREGS) – Revision of Rural Standard Schedule of Rates 2020-2021 (RSSR 2020-2021) – Orders – Issued.

PANCHAYAT RAJ AND RURAL DEVELOPMENT (RD.II) DEPARTMENT

G.O.MS.No. 616 **Dated: 03-04-2020**

Read the following:

1. G.O.Ms.No.102, PR&RD (RD.II) Dept,, Dated:21.05.2019
2. Notification No S.O.1203(E) Dt.23.03.2020 of GoI, MoRD, New Delhi.
3. From the Commissioner, Panchayat Raj & Rural Development e-file No.3646/EGS/SPM(T)/2016 Dt.30.03.2020.

<<0>>

ORDER:

In the G.O first read above, Government have issued orders modifying Rural Standard Schedule of Rates from Rs.205/- to Rs.211/- per day for the year 2019-2020 as per the wage rate enhanced by the Government of India under MGNREG Scheme for the year 2019-2020.

2. In the reference third read above, the Commissioner, Panchayat Raj & Rural Development, AP has submitted a proposal to Government for enhancement of task rates of Rural Standard Schedule of Rates for the Financial Year 2020- 2021, based on the wage rate enhanced by the Government of India in the reference second read above from Rs.211/- to Rs.237/- per day for the Financial Year 2020-2021.

3. Government after careful examination of the proposal, hereby enhance the task rates of Rural Standard Schedule of Rates for the Financial Year 2020-2021 as detailed in the Annexure to this order based on the wage rate enhanced by the Government of India from Rs.211/- to Rs.237/- for the Financial Year 2020-2021.

4. The Commissioner, Panchayat Raj and Rural Development, AP shall take necessary further action in the matter.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

GOPAL KRISHNA DWIVEDI
PRINCIPAL SECRETARY TO GOVERNMENT

To:
The Commissioner, Panchayat Raj and Rural Development, AP., Tadepalli, Guntur District with a request to communicate the same to all the concerned.
All the District Collectors and District Programme Coordinators, NREGS in the State.
All the Project Directors, DWMA & Addl. District Programme Coordinators, NREGS in the State.
All the Project Directors, DRDAs and Additional District Programme Coordinators, NREGS in the State.
All the Chief Executive Officers, ZPs and Additional District Programme Coordinators, NREGS in the State.
The Project Officer, ITDA and Additional District Programme Coordinators of Parvathipuram (Vizianagarm), Srisailam (Kurnool), Paderu (Visakhaptnam), Seethampeta (Srikakulam), Rampachodavaram (East Godavari) & KR Puram (West Godavari)

Copy to:
The PS to Prl. Secretary, PR & RD.

The PS to Prl. Secretary, Irrigation (I&CAD).
The PS to Prl. Secretary, Tribal Welfare Dept.
The PS to Prl Secretary, R&B.
The PS to Prl. Secretary, EFS & T Dept.
The PS to Prl. Chief Conservator of Forests.
The PS to Commissioner Disaster Management.
The PS to Commissioner, Tribal Welfare.
The PS to Engineer-in-Chief, Panchayat Raj Dept.
The PS to Engineer-in-Chief, Irrigation Dept.
The PS to Chief Engineer, Tribal Welfare Dept.
The Secretary, APSEG Council.
The PS to Hon'ble Minister (PR&RD, M&G).
SF/SC.

//FORWARDED :: BY ORDER//

SECTION OFFICER

ANNEXURE

(GO Ms.No.616, PR&RD (RD-II) Department, dated :03.04.2020)

Sl No	Category No.	Item of Work	Rates approved in RSSR (GO.Ms.No. 102, PR&RD (RD-II)Dept., dated 21.05.2019 (in Rs.)	Rates now approved to ensure maximum wage of Rs. 237/- (in Rs.)	Remarks
1		**Unskilled Labour**	211.0/ per day	237.00/ per day	-
2	**Bush clearance**				
	a	Light shrub	5.22/ sqm	5.86/ sqm	-
	b	Medium and Dense Shrub /Besharam/ Rubber plants	6.61/sqm	7.42/sqm	-
	c	Thin stemmed Juliflora (stem with periphery upto 150 cms)/ thick shrub	12.18/sqm	13.68/sqm	Thick shrub is relevant in tribal areas only
	d	Thick stemmed Juliflora (stem with periphery more than 150 cms	19.68/sqm	22.11/sqm	-
3	**Removal of stumps**				
	a	Removal of stumps of girth 30cms to 99cms(small stumps)	152.37 per each	171.15/per each	-
	b	Removal of stumps of girth 100cms to 199cms(medium stumps)	171.39 per each	192.51/per each	-
	c	Removal of stumps of girth 200cms to 299 cms(large stumps)	222.80 per each	250.25/per each	-
	d	Removal of stumps of girth 300cms to 399 cms(large stumps)	291.38 per each	327.28/per each	-
	e	Removal of stumps of girth 400cms to 499 cms(large stumps)	377.09 per each	423.56/per each	-
	f	Removal of stumps of girth 500cms to 599 cms(large stumps)	462.76 per each	519.78/per each	-
4		Removal of water hycinth up to 30cms thick	6.49 /Sqm	7.29/Sqm	-
5		Removal of water hycinth of more than 30cms thick	8.88/Sqm	9.97/Sqm	-
6	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in loamy and clayey soils like black cotton soils, red earth and chowdu soils (Ordinary soils)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	124.24/ Cum	139.55/Cum	-
	b	Category II (Trench Cutting works)	211/ Cum	237.00/Cum	-
	c	Category III (ponds) up to 1.00 m depth	243.08/ Cum	273.03/Cum	-
	d	Category III (ponds) beyond 1.00 m depth	260.10/ Cum	292.15/Cum	-
	e	Category IV (Pitting works)	179.29/ Cum	201.38/Cum	-
	f	Category V (Desilting works)	124.24/ Cum	139.55/Cum	-
7	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in Hard soils like gravel, moram., (Hard soils)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	211.00/ Cum	237.00/Cum	-
	b	Category II (Trench Cutting works)	237.31/ Cum	266.55/Cum	-

	c	Category III (ponds) up to 1.00 m depth	274.09/ Cum	307.86/Cum	-
	d	Category III (ponds) beyond 1.00 m depth	309.53/ Cum	347.67/Cum	-
	e	Category IV (Pitting works)	211/ Cum	237.00/Cum	-
8	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soils with mixture of gravel, pebble and soft disintegrated rock like shales ordinary gravel, stoney earth and earth mixed with fair sized boulders (Stoney earth)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	222.70/ Cum	250.14/Cum	-
	b	Category II (Trench Cutting works)	232.07/ Cum	260.67/Cum	-
	c	Category III (ponds) up to 1.00 m depth	321.40/ Cum	361.00/Cum	-
	d	Category III (ponds) beyond 1.00 m depth	334.91/ Cum	376.18/Cum	-
	e	Category IV (Pitting works)	222.70/ Cum	250.14/Cum	-
9	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soft disintegrated rock soils (removable by pick axes and crow bars) (SDR Soils)**				
	a	Category-I (All works other than trenches, ponds & plantation pitting)	237.31/ Cum	266.55/Cum	-
	b	Category II (Trench Cutting works)	281.30/ Cum	315.96/Cum	-
10	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in silt in canals, channels and drains**				
	a	Feeder/Field Channel and Irrigation drains upto 1.0 mt depth	92.24/ Cum	103.61/Cum	-
	b	Renovation of spring channels			
11	**Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in sandy soils or loose soils/wet sand not under water**				
	a	Land levelling for land development and Flood control Project	69.70/ Cum	78.29/Cum	-
12	a	Benching with 0.45mx 0.45m size and 0.60mx0.30m size	31.59/ Rmt	35.48/Rmt	-
13	**Carrying of earth / gravel by head loads – Leads & Lifts**				
	a	For every additional Lead of 10 mts over and above initial lead of 10mt	26.32/ Cum	29.56/Cum	-
	b	For every additional lift of 1mt over and above initial lift of 2mts	26.32/ Cum	29.56/Cum	-
14		Labour charges for Spreading of silt unloaded by tractor in the field	25.59/ Cum	28.74/Cum	-
15		Labour charges for breaking clods, trimming, sectioning and manual compaction using Dimmisa	39.86/ Cum	44.77/Cum	-
16	**Pebble bunding**				
	a	Small stone (size more than 40mm) bunding-Labour charges for collecting and putting as bund only.	276.87/ Cum	310.99/Cum	-
17	**Rough Stone Dry Packing & Stone pitching (Unskilled)**				
	a	Rock Fill Dam, Stone Checks & Stone outlets – Labour charges for packing only.	263.69/ Cum	296.18/Cum	-
	b	Stone Terracing – Labour charges for packing only.	263.69/ Cum	296.18/Cum	-
	Plantation works				

18	**Category : I**				
	a	Survey and demarcation	34.22/- per100 nos	38.44/- per100 nos	-
	b	Alignment and fixing of planting point with 0.45 meters length sticks	98.80/- per100 nos	110.97/- per100 nos	-
	c	0.45 meter sticks preparation and transportation at site.	52.68/- per100 nos	59.17/- per100 nos	-
	d	i) Internal transportation of bag plants to planting points. (5"x9")	52.68/- per100 nos	59.17/- per100 nos	-
		ii) Internal transportation of Avenue Plantation. Tall plants	204.61/- per100 nos	229.82/- per100 nos	-
	e	Refilling of Pits and planting (mxmxm), staking stick			
		i) 0.30 X 0.30 X 0.30 Size pit	1.22/- each	1.37/- each	-
		ii) 0.45 X 0.45 X 0.45 Size pit	3.85/- each	4.32/- each	-
		iii) 0.60 X 0.60 X 0.60 Size pit	7.85/- each	8.82/- each	-
		iv) 0.90 X 0.90 X 0.90 Size pit	11.77/- each	13.22/- each	-
		v) 1.00 X 1.00 X 1.00 Size pit	13.13/- each	14.75/- each	-
	Soil working and weeding				
	Category : I (1 M dia and 0.1 m Depth)				
	a	Avenue Plantation	13.13/- each	14.75/- each	-
	b	Horticulture	13.13/- each	14.75/- each	-
	Category : II (0.5 M dia and 0.1 m Depth)				
	a	Fore shore plantation	3.87/- each	4.35/- each	-
	b	B.H.Afforestation	3.87/- each	4.35/- each	-
	c	Bio Diesel Plantation & Block plantation	3.87/- each	4.35/- each	-
19	**Causality Replacement for**				
	a	Reopening of Pits for avenue, Horticulture & Blok Plantations.	13.35/- each	15.00/- each	-
	b	Fore share plantation, Barren Hill Afforestation, Bio-Diesel	6.49/- each	7.29/- each	-
20		Watch & Ward and repair to Fence and soil working of each plant including pruning of branches for plantations raised in common property resource lands and lands of SC/ST/assignees.	211/- day	237.00/- day	-
21	**Bio Fencing / Brush Wood Fencing for barren hill afforestation.**				
	a	Nurseries, block plantation and fore shore plantation including collection, transportation and fixing at site	26.30/- Rmt	29.54/- Rmt	-
	b	Avenue Plantation including collection, transportation and fixing at site (Size of 1 m dia and 1.5 m height)	99.76/- each	112.05/- each	-
	c	Horticulture, for lands of SC-ST & Assignee lands only	2637.17/- acre	2962.13/- acre	-
	d	Horticulture fencing 1st year & 2nd year maintenance SC-ST& Assignee lands only.	659.26/- acre	740.50/- acre	-
22	**Deep Ploughing in**				
	a	Fallow Land and Hard Gravel soils (Depth not less than 0.3 meters) using ploughing tractors	1742.96/- acre	1957.73/- acre	-
	b	fallow land in ordinary soils using ploughing tractor depth not less than 0.3 m	1394.83/- acre	1566.7/- acre	-
	c	Cattle cultivator (Double ploughing) in ordinary soils.	1047.41/- acre	1176.47/- acre	-

23		Watering plants of block plantation from the sump constructed (where ever one sump is available per one acre)	3.33/- plant	3.74/- plant	-
24		Watering plants from hand pump/bore well/open well up to distance of 30 mt	4.69/- plant	5.27/- plant	-
25		Watering block plantation from the nearby sources i.e bore well open well or kunta beyond 30 mts distance.	5.85/- plant	6.57/- plant	-
26		Hire charges of tractor mounted water tanker for filling sump	523.94/- per one trip of 5000 ltrs capacity	588.5/- per one trip of 5000 ltrs capacity	-
27		Sharpening of crowbar	15/- per day	15/- per day	**No change**
28		Basket Replenishment charges	5.50/- per day	5.50/- per day	**No change**

GOPAL KRISHNA DWIVEDI
PRINCIPAL SECRETARY TO GOVERNMENT